

計 算 表

愛木町4号線

①	掘削	0.0 m ³
②	床堀	30.9 m ³
③	埋戻	19.9 m ³
④	盛土	0.0 m ³

残土 = 30.9 - 19.9 ÷ 0.9 = 8.79m³

測点	単距離	断 面				平均断面				立 積				適要
		①	②	③	④	①	②	③	④	①	②	③	④	
-2.50	0.00	0.0	0.0	0.0	0.0									
B.P	2.50	0.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00	0.0	0.0	0.0	0.0	
B.P	0.00	0.0	0.4	0.2	0.0	0.00	0.20	0.10	0.00	0.0	0.0	0.0	0.0	
+12.50	12.50	0.0	0.3	0.1	0.0	0.00	0.35	0.15	0.00	0.0	4.4	1.9	0.0	
+12.50	0.00	0.0	0.5	0.3	0.0	0.00	0.40	0.20	0.00	0.0	0.0	0.0	0.0	
NO.1	7.50	0.0	0.5	0.3	0.0	0.00	0.50	0.30	0.00	0.0	3.8	2.3	0.0	
+4.00	4.00	0.0	0.5	0.3	0.0	0.00	0.50	0.30	0.00	0.0	2.0	1.2	0.0	
+10.00	6.00	0.0	0.5	0.3	0.0	0.00	0.50	0.30	0.00	0.0	3.0	1.8	0.0	
NO.2	10.00	0.0	0.5	0.3	0.0	0.00	0.50	0.30	0.00	0.0	5.0	3.0	0.0	
+7.50	7.50	0.0	0.4	0.3	0.0	0.00	0.45	0.30	0.00	0.0	3.4	2.3	0.0	
NO.3	12.50	0.0	0.4	0.3	0.0	0.00	0.40	0.30	0.00	0.0	5.0	3.8	0.0	
+4.80	4.80	0.0	1.4	1.2	0.0	0.00	0.90	0.75	0.00	0.0	4.3	3.6	0.0	
小計	67.30									0.0	30.9	19.9	0.0	

計 算 表

愛木町4号線

⑤ 路盤不陸修正	177.4 m ²
	0.0 m ²
	0.0 m ²
	0.0 m ²

測点	単距離	断 面			平均断面				立 積			適要	
		⑤			⑤				⑤				
-2.50	0.00	8.0											
B.P	2.50	4.2			6.10				15.3				
B.P	0.00	3.2			3.70				0.0				
+12.50	12.50	3.0			3.10				38.8				
+12.50	0.00	2.1			2.55				0.0				
NO.1	7.50	2.1			2.10				15.8				
+4.00	4.00	2.2			2.15				8.6				
+10.00	6.00	2.1			2.15				12.9				
NO.2	10.00	2.1			2.10				21.0				
+7.50	7.50	2.1			2.10				15.8				
NO.3	12.50	2.2			2.15				26.9				
+4.80	4.80	7.1			4.65				22.3				
小計	67.30								177.4	0.0	0.0	0.0	

