

数 量 総 括 表									
-----------	--	--	--	--	--	--	--	--	--

[illegible]

計 第 表 舗装工					計 算 表					
測 点	距 離	表層（改質Ⅱ型）			オーバーレイ工（t=3cm）					
		巾	平 均	平 積	巾	平 均	平 積	巾	平 均	平 積
NO. 0		7.00								
NO. 1	20.0	7.10	7.05	141.0						
NO. 2	20.0	7.50	7.30	146.0						
NO. 3	20.0	7.30	7.40	148.0						
NO. 4	20.0	7.50	7.40	148.0						
NO. 5	20.0	7.00	7.25	145.0						
NO. 6	20.0	6.50	6.75	135.0						
NO. 7	20.0	6.30	6.40	128.0						
NO. 8	20.0	6.30	6.30	126.0						
NO. 9	20.0	6.80	6.55	131.0						
NO. 10	20.0	7.10	6.95	139.0						
NO. 11	20.0	7.10	7.10	142.0						
NO. 12	20.0	7.10	7.10	142.0						
NO. 13	20.0	7.00	7.05	141.0						
NO. 14	20.0	6.60	6.80	136.0						
NO. 15	20.0	6.40	6.50	130.0						
NO. 16	20.0	6.40	6.40	128.0						
NO. 17	20.0	7.10	6.75	135.0						
NO. 18	20.0	7.50	7.30	146.0						
NO. 19	20.0	7.50	7.50	150.0						
NO. 20	20.0	7.40	7.45	149.0						
NO. 21	20.0	7.40	7.40	148.0						
NO. 22	20.0	7.40	7.40	148.0						
NO. 23	20.0	7.40	7.40	148.0						
NO. 24	20.0	7.40	7.40	148.0						
NO. 34		7.40	－	－						
NO. 35	20.0	7.40	7.40	148.0						
NO. 36	20.0	7.40	7.40	148.0						
NO. 37	20.0	7.40	7.40	148.0						
NO. 38	20.0	7.40	7.40	148.0						
NO. 38+10.0	10.0	7.40	7.40	74.0	7.40	－	－			
NO. 39	10.0				7.40	7.40	74.0			
計	580.0			4044.0			74.0			

計 第 表 区画線工 計 算 表										
測 点	距 離	区画線 (W=15)			区画線 (W=15)					
				延長						
NO. 0										
NO. 1	20. 0			60. 0						
NO. 2	20. 0			60. 0						
NO. 3	20. 0			60. 0						
NO. 4	20. 0			60. 0						
NO. 5	20. 0			60. 0						
NO. 6	20. 0			60. 0						
NO. 7	20. 0			60. 0						
NO. 8	20. 0			60. 0						
NO. 9	20. 0			60. 0						
NO. 10	20. 0			60. 0						
NO. 11	20. 0			60. 0						
NO. 12	20. 0			60. 0						
NO. 13	20. 0			60. 0						
NO. 14	20. 0			60. 0						
NO. 15	20. 0			60. 0						
NO. 16	20. 0			60. 0						
NO. 17	20. 0			60. 0						
NO. 18	20. 0			60. 0						
NO. 19	20. 0			60. 0						
NO. 20	20. 0			60. 0						
NO. 21	20. 0			60. 0						
NO. 22	20. 0			60. 0						
NO. 23	20. 0			60. 0						
NO. 24	20. 0			60. 0						
NO. 34										
NO. 35	20. 0			60. 0						
NO. 36	20. 0			60. 0						
NO. 37	20. 0			60. 0						
NO. 38	20. 0			60. 0						
NO. 38+10. 0	10. 0			30. 0		-				
NO. 39	10. 0			30. 0						
計	580. 0			1740. 0						

市道ゆずりは線舗装工事 数量計算書 交通誘導員			
工種	数量	配置人数 日当り作業量	
路上路盤再生工	4044	790	5.12
表層工	4044	2300	1.76
			6.88
			≒7日
区画線工	1740	1000	1.74
小計			≒9日
配置個所数	9	9日×3.0か所	27人