

令和8年度

市道小白府線舗装補修工事

当初

数量計算書

上 山 市

上段:当初 下段:變更

[illegible]

数量計算書

○舗装工

測点 (起点側)	起点からの 延長(m)	幅員 (m)	測点 (終点側)	延長 (m)	平均幅員 (m)	面積 (m2)
No.0	0.0	16.1	No.1	20.0	11.60	231.9
No.1	20.0	7.1	No.2	20.0	7.18	143.5
No.2	40.0	7.3	No.3	20.0	6.47	129.3
No.3	60.0	5.7	No.4	20.0	4.93	98.6
No.4	80.0	4.2	No.5	20.0	4.31	86.2
No.5	100.0	4.4	No.6	20.0	5.14	102.7
No.6	120.0	5.8	No.7	20.0	5.49	109.7
No.7	140.0	5.1	No.8	20.0	4.71	94.2
No.8	160.0	4.3	No.9	20.0	4.13	82.5
No.9	180.0	4.0	No.10	20.0	4.90	98.0
No.10	200.0	5.8	No.11	20.0	5.29	105.7
No.11	220.0	4.7	No.12	20.0	4.78	95.6
No.12	240.0	4.8	No.13	20.0	6.05	120.9
No.13	260.0	7.3	No.14	20.0	6.12	122.4
No.14	280.0	5.0	No.15	20.0	4.98	99.5
No.15	300.0	5.0	No.16	20.0	4.84	96.7
No.16	320.0	4.7	No.16+7.4	7.4	4.55	33.7
No.16+7.4	340.0	4.4				
合計				327.4		1851.1
平均		5.9				

○舗装版破碎

$$1851.1 \quad = \quad 1851.1 \text{ m}^2$$

○舗装殻

$$1851.1 \quad \times \quad 0.05 \quad = \quad 92.6 \text{ m}^3$$

(厚さm)

○舗装版切断

起点	16.1		終点	4.4
			計	20.5 m